

Certificate of Test

WALL TIE TESTS TO AS/NZS 2699.1:2000

Sponsor : Abey Australia Pty Ltd
PO Box 985
MELTON VIC 3337

Job Number : Job number CZ56BTS3092

Description : Face Fixed (Medium Duty Sherrif) Veneer Ties made out of 0.9mm thick galvanised strips and fixed with 8# 30mm Bugle Head Self Drilling Screws


Test Description The wall ties were tested in accordance with AS/NZS 2699.1:2000 (Built-in components for masonry construction – Part 1: Wall Ties) and evaluated using the performance requirements of Australian Standard AS 3700 – 1998 (Masonry Structures).

Test Date : 28 March 2001

Classification : The ties satisfy the requirements of AS 3700 for Medium Duty classification at a nominal cavity width of 50mm.

Tested by : Sam Samarasinghe (Senior Research Scientist)
& Geoff Farrance (Laboratory Manager)

Issued on 17 May 2001 without alteration or addition.



Dr Sam Samarasinghe
Project Leader - Structures
For Chief, DBCE



Improving the Built Environment